




515 N. Main Street | Hinesville, GA 31313
PO Box 649 | Hinesville, GA 31310
912.368.5212
www.mesack.com
ME Sack Engineering
@mesackengineering
mesack



ADDENDUM No. THREE

Date: June 19, 2025

Project: Pembroke WWTP Expansion, MES No. 2020-48

Engineer: M.E. Sack Engineering
Hinesville, Georgia 

The following clarifications are offered for questions received:

1. *Please advise if the ATS is service rated or not.*
 - We show a service entrance rated main service breaker upstream of the ATS-MSB, so the ATS will not need to be service entrance rated. See sheet E12.0 of the plan set.
2. *The spec states that the chemical feed skids need to feature Sigma 2 16050PVT pumps then incorrectly states 15.8GPM which should be 15.8GPH. The Sigma 2 16050PVT pumps are rated at 16.1GPH.*
 - Addendum #2 included a revised specification, Section 15280 Chemical Feed System, with the correct flow.
3. *The spec wants 3/4" PVC piping for feed systems.*
 - Addendum #2 included a revised specification, Section 15280 Chemical Feed System, with the correct pipe size.

-END-